

Stage 01: Proposal

0390:

Introduction of a Supply Point Offtake Rate Review and Monitoring Process.

What stage is this document in the process?



Proposal



Workgroup Report



Draft Modification Report



Final Modification

Implementation of this Modification Proposal would require Transporters and Shippers to review Supply Point Offtake Rates on an annual basis to ensure their continued validity. The Proposal would also require Shippers to ensure they have in place a process to monitor instances of a reduction in the maximum offtake rate and where necessary apply for a revised Supply Point Offtake Rate accordingly.



The Proposer recommends that this modification should be subject to development.



High Impact:



Medium Impact:

Transporters, Shippers and End Consumers.



Low Impact:

0390

Modification

19 September 2011

Version 2.0

Page 1 of 20

# Contents

- **1** Summary
- **2** Why Change?
- **3** Solution
- 4 Relevant Objectives
- 5 Impacts and Costs
- **6** Implementation
- **7** The Case for Change
- 8 Legal Text
- 9 Recommendation

# 8

3 Any questions?

5 Contact:

Joint Office



13

20

11

15 0121 623 2115

16 Proposer:

Joel Martin

17 **O**joel.martin@sgn.

co.uk



# About this document:

This document is a proposal, which will be presented by the Proposer to the Panel on July 21st 2011. The Panel will consider the Proposer's recommendation, and agree whether this modification should proceed to consultation or be referred to a Workgroup for assessment.



Transporter: Scotland Gas Networks



co.ul



xoserve: **Insert name** 



<u>commercial.enquiries</u> @xoserve.com



0390

Modification

19 September 2011

Version 2.0

Page 2 of 20

# 1 Summary

### Is this a Self-Governance Modification

Whilst SGN recognise that the implementation of this Modification Proposal may have a material impact on existing or future gas consumers and also the operation of one or more pipeline systems, it is recommended that the Self Governance process be employed. The justification for this recommendation relates to the fact that this UNC Modification Proposal introduces measures to improve processes associated with existing UNC obligations and that the proposed SPOR process has been previously discussed at (a) UNC Review Group 0329 with Users and Consumer representatives and has incorporated views from both GTs, Users & End Consumer representatives. It is further planned that this Modification Proposal be discussed at the Distribution Workgroup to further refine the business rules where necessary, in association with Users and Consumer representatives.



URL Link to Ofgem decision letter on SGN's GDPCR Capex re-opener

http://www.ofgem.gov.uk /Networks/GasDistr/GDPCR7 13/Documents1/ SGN\_LTS\_Authority\_Decisio \_letter.pdf

# Why Change?

Following the publication in March 2010 of Ofgem's decision letter relating to Scotland Gas Networks' (SGN) application to re-open the current Gas Distribution Price Control , which provided an approval to an adjustment to the interruption incentive allowance to facilitate specific network re-enforcement projects, SGN raised a UNC Review Modification Proposal (0329) which considered whether changes were required to the UNC processes around the incentives in place on Shippers to provide usage reflective Supply Point Offtake Rates (SPOR).

The Ofgem decision letter outlined concerns in relation to the current incentives in place to obligate Shippers to provide actual usage reflective SPORs and also that current capacity charges were broadly independent of the contracted SPOR despite the fact that the SPOR value may require Transporters to incur additional investment costs to meet these capacity requirements.

This Modification Proposal seeks to address these specific concerns and also to reflect the resulting output from the UNC Review Group in terms of modifying the regime to improve the SPOR review and monitoring process between Shippers and Transporters.

#### **Solution**

This UNC Modification Proposal seeks to introduce new obligations on both Transporters and Shippers to review Supply Point Offtake Rates for Daily Metered Supply Points on an annual basis to ensure they accurately reflect end consumer capacity requirements.

This UNC Modification would also introduce obligations on Shippers to apply for a revised SPOR where they became aware that the maximum offtake rate at a Registered DM Supply Point Component may be or has been subject to any reduction and also to take 0390 all reasonable steps to ensure they become aware of any such reduction in the SPOR.

It is not the intention of this UNC Modification proposal to cause SPORs to fluctuate on an annual basis linked to actual usage, but to ensure the SPOR is an accurate reflection, year on year, of potential maximum hourly capacity requirements.

Modification

19 September 2011

Version 2.0

Page 3 of 20

# **Impacts & Costs**

The SPOR annual review process would place additional costs directly on Transporters and Shippers to ensure compliance with the additional obligations this UNC Modification Proposal would introduce.

There would be an additional cost in relation to the requirement placed upon Transporters to generate individual Shipper SPOR reports detailing contractual values against actual usage values and also network planning / analysis costs related to the interpretation a these reports.

Shippers would incur additional costs linked to the implementation of internal processes to review Transporter generated SPOR reports. However, in relation to ensuring Shippers becoming aware of reductions in the SPOR, the UNC already requires Shippers to ensure they have processes in place to monitor increases in the maximum offtake rate at a DM Supply Points and therefore it is the proposer's view that incorporating a SPOR reduction monitoring process would not introduce additional cost.

# **Implementation**

This UNC Modification Proposal requires an Authority decision date by the 30th September 2011 and an implementation date of 3<sup>rd</sup> of October 2011 to allow the necessary work to be undertaken in relation to the administrative processes required to support the SPOR review process for April 2012.

# **The Case for Change**

The implementation of this UNC Modification Proposal would further the relevant objectives as described in Section 4 of this Modification Proposal.

#### **Recommendations**

SGN would recommend that this Modification Proposal is discussed at the July 2011 Distribution Workgroup if the UNC Modification Panel considers additional development may be required.

0390

Modification

19 September 2011

Version 2.0

Page 4 of 20

# 2 Why Change?



During the discussions held within the UNC Review Group 0329 (Review of Industry Charging and Contractual Arrangements - DM Supply Point Offtake Rates (shqs) and DM Supply Point Capacity (soqs)) SGN provided evidence which indicated that within the three Local Distribution Zones (Scotland, South East and Southern) operated by SGN there were a number of Daily Metered Supply Points which had either exceeded their contracted SPOR or had, over the previous gas year, used less than their contracted SPOR.

#### **Insert heading here**

Use this column in a Q and A style for explanations, in order to preserve the flow of the main text.

Insert text here

Gas Distribution Network Operators utilise Supply Point Offtake Rate information provided by gas Shippers to meet certain legislative requirements placed upon them to ensure the operation of a safe and economic gas transportation system. Requirements stipulated under the Gas Safety (Management) Regulations and reflected in transporters' safety cases set out arrangements for the minimisation of the risk of a gas supply emergency.

Network planning and analysis activities are a key element through which transporters demonstrate to Ofgem and the Health & Safety Executive (HSE) such arrangements to meet these regulatory legislative requirements. Network planning and analysis use complex modelling techniques to simulate the performance of the gas transportation networks and any alterations required to develop such networks. Gas transporters need to be able to demonstrate to both Ofgem and the HSE that the simulation models used in these processes are fully robust and can be fully relied upon to meet the requirements placed upon the gas network by Shippers and ultimately end users.

The SPOR is a key data element used in the construction and operation of network analysis models and the importance placed upon accurate SPORs is reflected in the recognition that DM Supply Points may place a non standard or disproportionate influence on the gas network compared to Non Daily Metered Supply points.

Where the SPOR is defined by the Shipper as being too high compared to the actual required offtake rate, this may result in:

- · Sterilisation of network system capacity
- Unnecessary general network re-enforcement resulting in unnecessary cost to the industry as a whole.
- Unnecessary specific network re-enforcement resulting in unnecessary cost to the end consumer.

Where the SPOR is defined by the Shipper as being too low compared to the actual required offtake rate, this may result in:

- Security of supply issues due to the gas network not being able to cope with the demand placed upon it.
- Safety issues related to failure to supply risk for the wider network.

0390

Modification

19 September 2011

Version 2.0

Page 5 of 20

# **Current UNC requirements in relation to SPORs.**

UNC TPD Section G 5.3 outlines the current obligations on Shippers to provide Supply Point Offtake Rates in relation to Daily Metered Supply Points. The SPOR is defined as the maximum instantaneous rate in kWh/hour that the User is permitted to offtake gas from the Total System at a DM Supply Point Component. Users are currently required to submit revised SPORs when they are:

- 1. submitting a Supply Point Nomination in respect of a Proposed Supply Point which includes a DM component;
- when submitting a Capacity Revision Application (whether to increase or in the Capacity Reduction Period to reduce its Supply Point Capacity) in respect of a Registered DM Supply Point Component; and
- 3. whenever the User becomes aware that the maximum offtake rate at a Registered DM Supply Point Component may be or has been subject to any increase.

Users are also required, when applying for a revised SPOR, to estimate the maximum offtake rate, in good faith and after appropriate enquiries with the customer using reasonable skill and care. The estimate used in such application should not be less than nor substantially more than such estimate (UNC TPD Section G 5.3.3).

Shippers are further required to take all reasonable steps to secure that they become aware of increases in the maximum offtake rate before and (in any event) as soon as reasonably practical after such event has occurred.

It is clear from the current UNC obligations that decreases (as opposed to increases) in the maximum offtake rate at a Supply Point may occur without a direct requirement for the User to amend the SPOR or to take reasonable steps to ensure that they become aware of such reduction at a DM Supply Point. In order to ensure SPOR decreases are reflected against a User's Registered DM Supply Point Component this UNC Modification Proposal looks to amend the current provisions within UNC TPD Section G 5.3 to ensure SPOR reductions are treated in the same manner as SPOR increases.

There are currently no obligations specified within the UNC which require Transporters to review SPORs in conjunction with Shippers to ensure the contracted SPOR figure is reflective of actual required hourly consumption at a DM Supply Point. Transporters currently have access (as do Shippers for their Registered DM Supply Points) to DM Supply Point hourly consumption for DM Supply Points located within their respective footprints. Analysis of this DM hourly consumption by SGN has indicated that actual hourly consumption may differ from the SPOR as registered against the Supply Point in the Sites and Meters database to the extent that SPORs may be significantly greater than or less than such registered SPOR value.

To ensure that Transporters are in possession of accurate registered contractual SPOR information (which can be reflected within network analysis models for the purposes developing the gas network) the solution detailed within this Modification Proposal would require Transporters and Shippers to review, on an annual basis, actual hourly consumption associated with DM Supply Points against the Supply Point Offtake Rate registered by the User under the provisions detailed in Section G.

0390

Modification

19 September 2011


Version 2.0

Page 6 of 20


# **Registered Supply Point Offtake Rate Information.**

The graphs detailed below indicate actual consumption at DM Supply Points within SGN's respective LDZs compared to the registered Supply Point Offtake Rate.


#### 1. Scotland LDZ:



#### 2. Southern LDZ:



#### 3. South Eastern LDZ:



0390

Modification

19 September 2011

Version 2.0

Page 7 of 20



This UNC Modification proposes two complementary solutions to the issue identified relating to the provision of accurate and usage reflective SPOR information at Daily Metered Supply Points by Users.

# Proposed revised UNC Obligation obligations.

# Insert heading here

Use this column in a Q and A style for explanations, in order to preserve the flow of the main text.

Insert text here

## Part 1:

The first part of the solution focuses on the revision of existing Supply Point Offtake Rates at DM Supply Points by extending the existing provisions specified in UNC TPD Section G 5.3.2 to obligate Shipper Users to apply for a revised SPOR where the User becomes aware of a decrease in the required maximum offtake rate. Current provisions also detail in UNC TPD Section G 5.3.4 a requirement on Users to monitor increases in the maximum offtake rate as a result of any changes in the size or nature of an end Consumer's Plant or the use of such Plant as soon as reasonably practicable after such increase occurs. This would be extended to include any decreases in the SPOR at a registered DM Supply Point.

#### Part 2:

The second part of the solution would introduce an additional obligation on Transporters and Shippers to review, on an annual basis, actual hourly consumption at DM Supply Points and compare such actual consumption data against a User's registered Supply Point Offtake Rate at the relevant DM Supply Point. Such a review would be facilitated via a report produced by Transporters which would detail the highest and lowest actual hourly consumption recorded at Supply Meter Points contained within a DM Supply Point Component throughout the previous winter period. The report would also detail the current registered Supply Point Offtake Rate provided by the relevant registered User of the DM Supply Point and the difference between this figure and the highest recorded actual hourly consumption. Where the Transporter considers that the registered SPOR differs significantly, either to the extent that it is significantly less than or significantly more than the highest actual hourly consumption at the DM Supply Point, the Transporter will indicate on the report to Users such a difference. It is recognised that spikes in hourly consumption may not necessarily be representative of normal operating conditions or requirements at a Supply Point and may, for example, be indicative of ad-hoc testing schedules for consumer's plant. Such information may be taken into consideration by the Transporters where this is made known by the User. However it should still be recognised that the SPOR is defined as the maximum instantaneous rate in kWh/hour that the User is permitted to offtake gas from the Total System.

The registered User at the relevant DM Supply Point, once in possession of the report, would discuss with the relevant end Consumer at the DM Supply Point the information provided within the report relating to the actual consumption recorded compared to the registered SPOR. Where it is determined by the registered User after such discussion that the SPOR requires to be revised to reflect required actual consumption, the registered User will apply for a revised Supply Point Offtake Rate accordingly. If

0390 Modification

Modification

19 September 2011

Version 2.0

Page 8 of 20

the registered User determines after such discussion with the end Consumer that it would not be appropriate to amend the SPOR in line with the information provided on the Transporter SPOR report or not to amend the SPOR in any event, then the User would be obliged to provide a suitable response specifying the reason or reasons to the Transporter why the SPOR would remain static.

Detailed business rules in relation to Part 2 of the proposal.

- 1. Transporters will derive a "SPOR" report on an annual basis.
- 2. The report will be compiled in April of each year by the Transporter after the current Ggas Yyear's winter period.
- 3. The report will be provided to the relevant Shipper by the Transporter by the end of April each year.
- 4. The report will specify, per DM Supply Point (where the data is available and the Transporter considers that the difference between SPOR and the highest recorded hourly actual consumption rate is material to the operation to the gas network):
  - The current registered Supply Point Offtake Rate (kWh / hour).
  - The highest hourly consumption value in kWh/hour recorded by the Transporters' relevant Daily Metered Service Provider throughout the current gas year's winter.
  - Information required to identify the specific DM Supply Point (mprn, supply point id and address).
  - Any further detail relating to the DM Supply Point the Transporter considers it
    would be appropriate to provide (and is permitted to provide) to assist the
    User during the review.
- 5. On a receipt of the report, Shippers shall enter into discussions with their end consumers or their representatives to discuss amending the SPOR based on the information provided by the Transporters in the SPOR report.
- 6. Shippers will provide a report (the Shipper SPOR report) to the Transporters within 3 calendar months in response to the Transporter SPOR report specifying the following:
  - For each DM Supply Point specified on the Transporter SPOR report; a planned revised SPOR for each DM Supply Point.
  - Where the planned revised SPOR differs from the highest actual hourly consumption, the Shipper shall provide a reason for such deviation.
  - Where the Shipper does not plan to submit a revised SPOR in any event, the Shipper shall provide information to the Transporter setting out detailed reasons for this decision.
- 7. Where the Shipper has identified that a revised SPOR is required the Shipper shall apply for a revised SPOR utilising the existing Capacity Revision Application process in line with the planned revised SPOR.
- 8. The Shipper will where applicable apply for a revised SPOR (by submitting a Capacity Revision Application) prior to the end of August in the current gas year. Where a reduction in the SPOR will require a reduction in the Supply Point Capacity the Capacity Reduction Period parameters will still apply, albeit the associated Capacity Revision Application should be submitted by the end of January in the following Gas Year.

0390

Modification

19 September 2011

Version 2.0

Page 9 of 20

- 9. The existing provisions detailed in UNC TPD Section G 5 relating to a Capacity Revision Application, Capacity Reduction Period and the Absolute Requirement (as specified in UNC TPD Section G 5.4) will remain unchanged.
- 10. For the avoidance of doubt NTS Supply Point Components are excluded from all provisions which would be introduced by the implementation of this UNC Modification Proposal.

0390

Modification

19 September 2011

Version 2.0

Page 10 of 20

# **4 Relevant Objectives**

The Proposer believes that implementation will better facilitate the achievement of **Relevant Objectives a, b, c, d, e and f.** 

Proposer's view of the benefits against the Code Relevant Objectives			S
	De	scription of Relevant Objective	Identified impact
	a)	Efficient and economic operation of the pipe-line system.	Yes
	b)	Coordinated, efficient and economic operation of  (i) the combined pipe-line system, and/ or  (ii) the pipe-line system of one or more other relevant gas transporters.	Yes
	c)	Efficient discharge of the licensee's obligations.	Yes
	d)	Securing of effective competition:  (i) between relevant shippers;  (ii) between relevant suppliers; and/or  (iii) between DN operators (who have entered into transportation arrangements with other relevant gas transporters) and relevant shippers.	Yes
	e)	Provision of reasonable economic incentives for relevant suppliers to secure that the domestic customer supply security standards are satisfied as respects the availability of gas to their domestic customers.	No
	f)	Promotion of efficiency in the implementation and administration of the Code	No



## **Insert heading here**

Use this column in a Q and A style for explanations, in order to preserve the flow of the main text.

Insert text here

# Better facilitates Relevant Objective (a) Efficient and economic operation of the pipe-line system.

Implementation of this Proposal would provide a process to facilitate the provision of more accurate and usage reflective SPORs by Users. This would enable Transporters to effectively plan the development of the distribution network system on a more efficient and economic basis. By avoiding investment in the system to meet over stated SPORs and instead targeting such investment towards more effectual projects the Transporters would be utilising capital investment in a more efficient and economic manner. Also, by facilitating a reduction in SPORs, where capacity is not required, the Transporters would be able to make available such capacity to other Users thus utilising existing capacity more effectively and avoiding capacity sterilisation. Reduced SPORs may also result in the option for Transporters to reduce gas network operating pressures which may facilitate reduced shrinkage volumes.

Under stated SPORs may result in the gas network being designed and planned to provide capacity which is insufficient to meet Users' actual requirements. Where such situations occur an adverse situation may arise on the gas network requiring a

0390

Modification

19 September 2011

Version 2.0

Page 11 of 20

reactionary response from the Transporter which may result in costs not otherwise required were accurate information to be initially provided.

# Better facilitates Relevant Objective (b) Coordinated, efficient and economic operation of (i) the combined pipeline system, and or (ii) the pipe line system of one or more relevant gas transporters.

In addition to the more efficient utilisation of the downstream (distribution) pipeline system, more accurate capacity requirements communicated by Users to the DN would result in more accurate and reflective NTS Exit capacity requirements. Accurate NTS Exit Capacity requirements would allow National Grid NTS to plan their pipeline system in a more efficient and economic manner.

# Better facilitates Relevant Objective (c) Efficient discharge of the licensee's obligations.

There are several references to the efficient and economic operation of the relevant pipeline system throughout the Transporters' licences. Provision of more accurate information by Shippers to Transporters relating to operational capacity requirements would facilitate efficient discharge of the relevant licence conditions.

# Better facilitates Relevant Objective (d) Securing effective competition (i) between relevant Shippers.

The provision of accurate SPOR information by Shippers will permit Transporters to plan their gas networks in a more efficient and economic manner by targeting investment on the physical network where investment is actually required, as opposed to meeting capacity requirements which may have been over stated. This in turn would facilitate the de-sterilisation of capacity allowing Users to access existing network capacity for new connections or capacity increases in timelier manner and also potentially at reduced cost, thus facilitating improved competition.

0390

Modification

19 September 2011

Version 2.0

Page 12 of 20

# 5 Impacts and Costs



Insert text here

#### **Costs**

Include here any proposal for the apportionment of implementation costs amongst parties.

Indicative industry costs – User Pays

Classification of the proposal as User Pays or not and justification for classification

Not User Pays. Implementation of this proposal may increase direct costs to Transporters in relation to the provision of new reports and analysis of SPOR information however the Proposer does not envisage any new services or costs which would be attributable to the Transporters' Agency.

Identification of Users, proposed split of the recovery between Gas Transporters and Users for User Pays costs and justification

N/A

Proposed charge(s) for application of Users Pays charges to Shippers

N/A

Proposed charge for inclusion in ACS – to be completed upon receipt of cost estimate from xoserve

N/A

# **Impacts**

Impact on Transporters' Systems and Pro	cess
Transporters' System/Process	Potential impact
UK Link	• No
Operational Processes	• Yes
User Pays implications	• No

Impact on Users	
Area of Users' business	Potential impact
Administrative and operational	• Yes
Development, capital and operating costs	• Yes
Contractual risks	• No
Legislative, regulatory and contractual obligations and relationships	• Yes

0390

Modification

19 September 2011

Version 2.0

Page 13 of 20



Where can I find details of the UNC Standards of Service?

mpact on Transporters	
Area of Transporters' business	Potential impact
System operation	• Yes
Development, capital and operating costs	• Yes
Recovery of costs	• No
Price regulation	• No
Contractual risks	• Yes
Legislative, regulatory and contractual obligations and relationships	• Yes
Standards of service	• No

Impact on Code Administration	
Area of Code Administration	Potential impact
Modification Rules	• No
UNC Committees	• No
General administration	• Yes

Impact on Code	
Code section	Potential impact
UNC TPD Section G 5	Yes – see suggested legal text.

Impact on UNC Related Documents and Other Referenced Documents	
Related Document	Potential impact
Network Entry Agreement (TPD I1.3)	None
Network Exit Agreement (Including Connected System Exit Points) (TPD J1.5.4)	Yes. Where a NeXA exists the agreement would need to reflect the change in SPOR / SPC.None
Storage Connection Agreement (TPD R1.3.1)	None
UK Link Manual (TPD U1.4)	None
Network Code Operations Reporting Manual (TPD V12)	None

0390

Modification

19 September 2011

Version 2.0

Page 14 of 20

Impact on UNC Related Documents and Oth	ner Referenced Documents
Network Code Validation Rules (TPD V12)	None
ECQ Methodology (TPD V12)	None
Measurement Error Notification Guidelines (TPD V12)	None
Energy Balancing Credit Rules (TPD X2.1)	None
Uniform Network Code Standards of Service (Various)	None

Impact on Core Industry Documents and ot	her documents
Document	Potential impact
Safety Case or other document under Gas Safety (Management) Regulations	None
Gas Transporter Licence	None

Other Impacts	
Item impacted	Potential impact
Security of Supply	None
Operation of the Total System	None
Industry fragmentation	None
Terminal operators, consumers, connected system operators, suppliers, producers and other non code parties	None

# 6 Implementation



This UNC Modification Proposal requires an Authority decision date by the 3<u>10stth</u> September <u>December</u> 2011 and an implementation date of <u>1st3<sup>rd</sup></u> of <u>October January</u> 201<u>2</u>1 to allow the necessary work to be undertaken in relation to the administrative processes required to support the SPOR review process for April 2012.

0390

Modification

19 September 2011

Version 2.0

Page 15 of 20

# 7 The Case for Change



In addition to that identified the above, the Proposer has identified the following:

## **Advantages**

The implementation of this Proposal would provide a basis for an enhanced Transporter to Shipper/end consumer operational relationship, providing a conduit for increased dialogue and discussion on the subject of capacity requirements and other operational matters.

# **Disadvantages**

None identified.

0390

Modification

19 September 2011

Version 2.0

Page 16 of 20

# 8 Legal Text

# **Suggested Text**

UNC TPD SECTION G.

#### **AMEND SECTIONS:**

# 5.3 Supply Point Offtake Rate

- 5.3.1 The "Supply Point Offtake Rate" in respect of a DM Supply Point Component is the maximum instantaneous rate (in kWh/hour) at which a User is permitted to offtake gas from the Total System at that Supply Point Component.
- 5.3.2 A User shall apply for a Supply Point Offtake Rate or revised Supply Point Offtake Rate:
  - (a) when submitting a Supply Point Nomination (as a Proposing User) in respect of a Proposed Supply Point which includes a DM Supply Point Component;
  - (b) when submitting a Capacity Revision Application (whether to increase or in the Capacity Reduction Period to reduce its Supply Point Capacity) in respect of a Registered DM Supply Point Component; and[1]
  - (c) whenever the User becomes aware that the maximum offtake rate at a Registered DM Supply Point Component may be or has been subject to any increase or or decrease; [2]
- 5.3.3 Wherever a User applies for a Supply Point Offtake Rate or a revised Supply Point Offtake Rate:
  - (a) the User shall estimate the maximum offtake rate, in good faith and after all appropriate enquiries of the consumer and on the basis of reasonable skill and care; and
  - (b) the Supply Point Offtake Rate for which the User applies shall be not less than, nor substantially more than, such estimate.
- A User shall take all reasonable steps to secure that it becomes aware of any increase or decrease (whether by reason of a change in the size or nature of, or the nature of the use of, the Consumer's Plant or otherwise) in the maximum offtake rate before and (in any event) as soon as reasonably practicable after such increase or decrease occurs (without prejudice to paragraph Error! Reference source not found. or Section J3.8).[3]
- 5.3.5 The Supply Point Offtake Rate prevailing at any time in respect of any DM Supply Point Component will be the Supply Point Offtake Rate specified in the Supply Point Offer, subject to any increase or decrease in such Supply Point Offtake Rate which has (at such time) been approved pursuant to paragraph Error! Reference source not found.
- 5.3.6 In this paragraph Error! Reference source not found., the "maximum offtake rate" is the maximum instantaneous rate (in kWh/hour) at which gas is or is likely to be offtaken from the Total System at a Registered DM Supply Point Component.

5.3.7 In relation to a DM Supply Point Component which comprises Shared Supply Meter Point(s), the maximum offtake rate is to be determined as at the time of the expected greatest instantaneous rate of offtake in aggregate at all of the DM Supply Point Components which comprise such Shared Supply Meter Point(s).

0390

Modification

19 September 2011

Version 2.0

Page 17 of 20

## **5.7** Supply Point Offtake Rate Review Process

- 5.7.1 In accordance with this paragraph 5.7, Transporters and Users undertake, in relation to DM Supply Point Components, to annually review the Supply Point Offtake Rate at a DM Supply Point (the "SPOR Review Process").[4]
- 5.7.2 The relevant Transporter, in respect of a DM Supply Point Component comprised in a LDZ Supply Point, shall provide to the Registered User of the DM Supply Point Component, prior to the last Business Day in April of each Gas Year, [5] an annual report, [6], detailing the information specified in paragraph 5.7.3 (the "Transporter SPOR Report").
- 5.7.3 The Transporter SPOR Report shall be complied in April of each Gas Year [7] and shall specify (where the data is available and where the Transporter considers appropriate) for each DM Supply Point Component [8]:
  - (a) the existing Supply Point Offtake Rate [9] for the time being held by the Registered User (the "Existing Supply Point Offtake Rate");
    - (b) the single highest hourly offtake rate (in kWh/hour) recorded at the DM

      Supply Point during a period covering the months from October to March

      (inclusive) during the current Gas Year;
  - (c) the Meter Point Reference Number;
  - (d) the Supply Point Reference Number;
  - (e) the address details; and
  - any further information relating to the DM Supply Point Component that the Transporter considers would assist the Registered User during the SPOR Review Process[11].
- 5.7.4 On receipt of the Transporter SPOR Report, the Registered User will enter into discussions with the relevant consumer or consumer's representative at each DM Supply Point to discuss the information detailed within the Transporter SPOR with a view to propose a revised Supply Offtake Rate ("Proposed Supply Offtake Rate"). [12]
- 5.7.5 For each DM Supply Point Component specified on the Transporter SPOR Report the Registered User shall provide to the relevant Transporter, prior to the last Business Day in July of each Gas Year, a report specifying:
  - (a) The Proposed Supply Point Offtake Rate; and
  - (b) where the Proposed revised Supply Point Offtake Rate is:
    - i. less than or greater than the single highest hourly offtake rate provided to the Registered User in accordance with paragraph 5.7.3 (b); or
    - ii. is the same as the Existing Supply Point Offtake Rate provided to the Registered User in accordance with paragraph 5.7.3 (a);

the reasons for this (the "Registered User SPOR Report").

5.7.6 [13]Where the Proposed Supply Point Offtake Rate shall amend the Existing Supply Point Offtake Rate, the Registered User shall apply for a revised Supply Point Offtake Rate in accordance with paragraph 5.3.2 (b), [14]prior to the last Business Day in August in the Gas Year, save for where a reduction in the Supply Point Capacity is also required at the DM Supply Point, then the Registered User shall apply for a revised Supply Point Offtake Rate in accordance in 5.3.2 (b) during 1 October to 31 January (inclusive) of the following Gas Year) [15]

5.7.7 The Transporter will reject any Proposed Supply Point Offtake Rate by the

0390

Modification

19 September 2011

Version 2.0

Page 18 of 20

Registered User of a DM Supply Point Component where the Supply Point Offtake Rate applied for under paragraph Error! Reference source not found. and the increased or reduced Supply Point Capacity are not in compliance with paragraph Error! Reference source not found. and/or 5.2.1. For these purposes the Supply Point Offtake Rate shall remain unchanged, however shall be subject to the SPOR Review Process in the following Gas Year. [16]

0390

Modification

19 September 2011

Version 2.0

Page 19 of 20

# 9 Recommendation

The Proposer invites the Panel to:

 DETERMINE that Modification 0390 progresses to the Distribution Workgroup on the 28<sup>th</sup> July 2011 for discussion / development.

0390

Modification

19 September 2011

Version 2.0

Page 20 of 20