BRAISHFIELD A MER SO002 Rev1

NULL METER ERROR REPORT

FINAL

Reconcile?	N	
Safety Issue?	N	
Thesis Report No.	N/A	

1. EXECUTIVE SUMMARY

SITE NAME	BRAISHFIELD A
LDZ	SOUTH
LAST GOOD DATE	29/12/09
START DATE	29/12/09
END DATE	21/01/10
SIZE OF ERROR (No reconciliation required if under 0.1%)	<0.1%
ESTIMATE – Y/N?	Ν
ROOT CAUSE	LDP loop errors
ANALYSIS	Appendix B
METER TYPE	ORIFICE
AUTHOR	T Roberts
CHECKED BY	

2. BACKGROUND

Gas is supplied to part of the SoE network at Braishfield A FWACV Offtake which employs an orifice plate meter to measure the volumetric flow rate in accordance with BS EN ISO 5167.

Following a lightning strike on 23/12/09 that damaged a large amount of equipment a re-commissioning ME2 validation was carried out to validate the metering system on 29/12/09. Further calibrations were carried out in January 2010 which recorded as-found errors to the 0 - 50mbar LDP loop. As a consequence the LDP transmitter s/n 8950-00764690022 was replaced by s/n E24333.

3. ERROR QUANTIFICATION AND IMPACT

Calibration results 21 Jan 2010

% Span	Tx error	ADC error	Loop error
0	0.52	-0.64	-0.13
25	0.89	-0.07	0.82
50	0.98	-0.07	0.91
75	1.00	-0.09	0.91
100	1.05	-0.10	0.95

Analysis of HPMIS data between 29/12/09 and 21/1/10 shows that on a number of Gasdays the low dp did not contribute to the in-use dp so these days have been excluded.

Four minute HPMIS data for the affected Gasdays was corrected for the LDP loop errors and then using GasVLe both uncorrected and corrected flow were calculated to provide the overall error for each Gasday.

Errors for all affected Gasdays were less than 0.1%, when divided by two as the timing of the drift is unknown. Results have been tabulated in Appendix A.

4. CAUSES

Calibration shift of both LDP transmitter and ADC in service following the lightning strike.

5. RECOMMENDATIONS AND LEARNING

It is a recommendation of this report that a 'Null' result be recorded.

REFERENCES HPMIS records Gemini records

ME2 calibrations

VERSION HISTORY

Version	Changes	Author	Date
Rev O	First draft	T Roberts	16/3/12
Rev 1	Final, no changes	T Roberts	10.4.12

DISTRIBUTION

Joint Office of Gas Transporters UKT Data assurance and Quality Team (NG) E Melen (SGN) B Purl (SGN) S Skipp (SGN)

BRAISHFIELD A MER SO002 Rev1

Appendix A

% error
0.0014
0.0001
0.0031
0.0034
0.0098
0.0126
0.0220
0.0371
0.0414
0.0808