Stage 02: Workgroup Report

0410 0410A:

Responsibility for gas off-taken at Unregistered Sites following New Network Connections At what stage is this document in the process?



02 Workgroup Report

03 Draft Modification Report

Final Modification Report

These modifications proposes to place an obligation on Gas Transporters and Shippers to take responsibility for any gas consumed at Unregistered Sites to reduce the likelihood of gas flowing at a New Supply Meter Point in the absence of a registered User.



The Workgroup recommends these modifications and legal text require further assessmentshould be issued to consultation.



High Impact: Transporters, Customers



Medium Impact: Shippers, Suppliers



Low Impact: N/a

0410

Workgroup Report

20 December 2012

Version 2.3

Page 1 of 27

Contents

- 1 Summary
- 2 Why Change?
- 3 Solution
- 4 Relevant Objectives
- 5 Impacts and Costs
- 6 Implementation
- 7 The Case for Change
- 8 Legal Text
- 9 Recommendation
- 10 Appendix 1 (0410A)

About this document:

The purpose of this report is make a recommendation to the Panel, to be held on 21 February 2013, on whether Modifications 0410 and 0410A are sufficiently developed to proceed to consultation and to submit any further recommendations in respect of the definition and assessment of these modifications.



3 Any questions?

7 Contact:

Joint Office

enquiries@gasgov ernance.co.uk

17

21



Proposer 0410:

22 **0410**: Andrew Green

23 (Total Gas & Power Ltd)

26 **0410A**:

27 andrew.green@tot algp.com

chris.warner@national grid.com



Proposer Representative for 0410:

Gareth Evans (Waters Wye Associates)



e.co.uk



Proposer 0410A:

Chris Warner (National Grid Distribution)



chris.warner@national grid.com



0410

Workgroup Report

20 December 2012

Version 2.3

Page 2 of 27

1 Summary

Is this a Self-Governance Modification

The Modification Panel determined these modifications were not suitable to be considered under the Self-Governance Process.

Why Change?

Currently Transporters have responsibility for MPRN creation, allocation and record keeping in relation to new service connections and, in accordance with industry processes, are informed of the installation of a meter from which point the Supply Point is capable of flowing gas. Further, where it appears that gas may be taken in the course of conveyance, Transporters have a licence requirement (SLC 7) to investigate and recover the value of gas so taken. Transporters ability to charge for gas taken in the course of conveyance is set out in the Gas Act, Schedule 2B para 9.

Suppliers and Shippers do not have the same rights and obligations, nor do they have control of network connection processes and are thus powerless to prevent the unauthorised (Unregistered) abstraction of gas prior to a shipper confirming ownership of the supply point through SPA processes. Suppliers / Shippers have no ability to recover gas taken at Unregistered Sites nor limit loss to the industry by disconnection without a Shipper first having confirmed ownership.

Unregistered Sites following new network connections are a significant source of Unidentified Gas (207GWh at last estimate¹). Where Transporter has control over the new connection process and the ability to limit loss and recover costs, the Transporter should be responsible and accountable for the consequences of any gas off-taken prior to shipper confirmation at a new connection to the network.

Where the Shipper requests the creation of an MPRN from the Transporter, that Shipper then has the ability to limit loss and recover costs through a contractual relationship with the infrastructure provider, and therefore that Shipper should be responsible and accountable for the consequences of any gas off-taken prior to shipper confirmation at a new connection to the network.

Note: for the purposes of this document the following definitions apply:

Shipperless site: A site that no longer has a shipper/supplier registered but could be still subject to the deemed contract rules in some circumstances

Unregistered site has never had a supplier/shipper responsible so there cannot be a deemed contract.

For Modification 0410A

Presently the UNC establishes that "no person shall be entitled to offtake gas from the Total System at a New Supply Meter Point at any time before the First Supply Point

¹ Allocation of Unidentified Gas Statement, version 4.0 December 23 2011

0410

Workgroup Report

20 December 2012

Version 2.3

Page 3 of 27

Registration Date". However there is evidence that an increasing number of Supply Meters are being installed, rendering the Supply Meter Point capable of flowing gas in the absence of a supply contract and associated User registration. Gas offtaken by consumers in these circumstances has a significant adverse financial consequence on the User community with the energy costs being borne by Users having Smaller Supply Points (SSPs) though the Reconciliation by Difference (RbD) mechanism and by Shippers having Larger Supply Points (LSPs) where a reallocation of energy is made by the Allocation of Unidentified gas Expert (AUGE).

Solution

Modification 0410

This modification proposes that Transporters should be responsible for, investigate and resolve Unregistered Sites following a new network connection where the Transporter has created the Meter Point Reference Number (MPRN) for any party other than a Shipper. If such an Unregistered Site has not either been assigned to a Shipper or disconnected following investigation by the Transporter, then the Transporter will be liable for the costs of the gas that the site has abstracted from the network. This modification also proposes to require that where Transporters become aware of a contracted supplier to an Unregistered Site, that they will make reasonable efforts to inform that contracted Supplier so that they may arrange for a shipper to register the site.

As the related siteworks contracts are outside of the remit of the UNC, this solution will leave it to the discretion of the Transporters, individually or collectively, to decide on the best control measures to put in place to prevent the flow of gas prior to shipper confirmation. We envisage that these could be similar to controls that exist in the electricity industry (where new connections must have a registered supplier prior to work commencing) or bespoke Gas industry processes could be developed.

Where a Shipper requests the creation of an MPRN from the Transporter, that shipper then has the ability to limit loss and recover costs through the contract it has with the siteworks provider, and therefore that Shipper should be responsible and accountable for the consequences of any gas off-taken prior to shipper confirmation at a new connection to the network.

Modification 0410A

It is proposed to introduce provisions to the UNC which require Users to ensure their Suppliers have valid supply contracts in place before commissioning the installation of a Supply Meter at a New Supply Meter Point. This will be accompanied by measures to secure that a New Supply Meter Point is either registered to a User or disconnected. Obligations on Transporters to investigate unregistered sites also feature.

Impacts & Costs

These modifications would minimise the amount of gas attributed to Unregistered Sites following siteworks.

The party empowered to manage the controls around new connections and the party

0410

Workgroup Report

20 December 2012

Version 2.3

Page 4 of 27

with rights to remedy where no shipper confirms ownership is the Transporter where the transporter has issued the MPRN and the Shipper where the Shipper has requested the creation of the MPRN from the Transporter. The costs would therefore be borne by the correct party.

Where this is the Transporter this would be in line with their responsibilities for providing a safe network, managing new connections processes, preventing and rectifying theft in conveyance and responsibility for gas taken in the course of conveyance. The costs to the industry and therefore end consumers will be less because gas consumed at Unregistered Sites would be minimised and it would reduce the amount of gas that is socialised across all customers. Also, Transporters would protect their transportation revenue for sites newly connected to the Network

Modification 0410A

Where the Shipper requests the creation of an MPRN from the Transporter, that shipper then has the ability to limit loss and recover costs through a contractual relationship with the end consumer.

Implementation of the proposed terms would reduce the overall population of 'unregistered sites' which has been highlighted as an industry concern in light of the risk of socialised costs being otherwise applied to the User community. The proposed method of achieving re-registration is an existing process operated by both Users and Transporters (including the capability for the Transporter to register on the User's behalf). Notwithstanding this, it is expected that systems, process and administration costs are likely to be incurred by Transporters.

Implementation

For Modification 0410

- 01 April 2013 if a decision is received prior to 01 December 2012 January 2013
- 01 April 2014 if a decision is received after 01 December 2012 January 2013 and prior to 01 December 2013

If a decision is received after 01 October 2013 implementation should occur for the following 1 April that is at least 6 months after the decision date.

For Modification 0410A

Systems changes are likely to be necessary to facilitate implementation of this modification. As part of its development, consideration will need to be given to identifying an optimum timetable for implementation. Consequently an implementation date is not identified at this point.

The Case for Change

These modifications should give the party who is in control of the industry processes and the remedies (ie investigating, escalating and ultimately disconnecting where end consumers do not find a shipper within an agreed timescale) the responsibility for the consequences of any gas abstracted from a supply point prior to a Shipper confirming

0410

Workgroup Report

20 December 2012

Version 2.3

Page 5 of 27

ownership.

Modification 0410A

This alternative modification has been raised to offer balanced contractual remedy to the enduring issue of 'unregistered sites'.

Recommendations

The Workgroup does not considers that these modifications are sufficiently developed to proceed to consultation and require further assessment by the Workgroup.

0410

Workgroup Report

20 December 2012

Version 2.3

Page 6 of 27

2 Why Change?

Modification 0410

At present, where the Transporter creates the MPRN, neither Suppliers nor Shippers have any direct control of the processes that relate to the new connection and nor do they have the authority to invoice for gas or disconnect a customer that they have not confirmed ownership of. Often Suppliers / Shippers are not involved at all and are unaware that a connection or meter installation has taken place. Shippers are therefore powerless to prevent the unauthorised and unpaid for abstraction of gas prior to a Supplier obtaining a supply contract with the end consumer and the Shipper confirming ownership of the supply point through SPA processes. The cost for any gas that is abstracted by these Unregistered Sites is inequitably borne by Shippers through the RbD and Unidentified Gas processes.

By contrast, Transporters have responsibility for MPRN creation and issue MPRNs to any party wishing to make future connections to their network (note this modification proposal excludes assigning Transporter responsibility for unregistered gas assigned to those MPRN's that are requested by Shippers/Suppliers). A connections company will then install the pipe-work and connection and label the connection with the MPRN that they have assigned to that connection. The network is then informed and the MPRN is recorded on their system. Following the installation of a meter, from which point the Supply point is capable of flowing gas, the network is informed and this is also recorded. The Transporter is also aware at the point that a Shipper confirms the site. As the party with oversight and control of this process therefore, any solution should look to require the Transporters to ensure that the number of Unregistered Sites is minimised and where no shipper confirmation follows the connection the site is investigated by Transporters and steps taken to limit loss to the industry.

Where a shipper requests an MPRN from a Transporter and the MPRN is effectively created by the Shipper, then this Shipper has the ability to ensure that they contractually able to control the future registration of that supply point. In this case it is appropriate for the requesting shipper should be responsible for any future unregistered gas associated with this MPRN until its first registration point.

For Modification 0410A

There is evidence that Supply Meters are installed at New Supply Meter Points in the absence of a supply contract between the consumer and Supplier.

The UNC TPD Section G establishes that:

7.3.3 Subject to paragraph 7.3.7, no person shall be entitled to offtake gas from the Total System at a New Supply Meter Point at any time before the First Supply Point Registration Date.

7.3.4 For the purposes of the Code, the "First Supply Point Registration Date" is the Supply Point Registration Date of the first Supply Point Registration to be made for a Supply Point comprising the New Supply Meter Point.

Therefore the UNC clearly contemplates that gas cannot be permitted to be offtaken at a Supply Point which is not registered to a User. However 'unregistered sites' are known to exist. Some sites can be legitimately unregistered, i.e. that a Supply Meter is installed but is not capable of flowing gas i.e. that a physical device is fitted preventing flow of gas. However, in other cases a Supply Meter may have been installed and

0410

Workgroup Report

20 December 2012

Version 2.3

Page 7 of 27

offtake of gas enabled but through process failure the consumer is offtaking gas in the absence of a Supplier and registered User. Alternatively a consumer may be contracting with a Supplier in good faith but the relevant User has not registered the Supply Point through process failure.

Only where a Supply Meter is installed can gas flow. Offtake of gas could not otherwise occur (other than in the case of an illegal connection to the service pipe). Modification 0410 seeks to place a responsibility on the party requesting the creation of an 'M' number to bear liability for a Supply Point where gas has flowed in the absence of User Registration. The Modification disregards the significance of the presence of the Supply Meter or a supply contract and focuses instead on the existence of a 'live' service pipe to a property. Thus a Transporter or User who requested the 'M' number could bear financial responsibility for energy flowing at an unregistered New Supply Meter Point even if a supply contract is in place and a Supply Meter has been installed at the request of a Supplier but where that Supplier's User has failed to register the Supply Point.



Unregistered sites

An unregistered site is a New Supply Meter Point which has never been registered to a User on the Supply Point Register.



Supply Meter Point Reference Numbers

A Supply Meter Point Reference ('M') Number is defined in UNC TPD Section G1.9.2(a). TPD Section G7.3.1. sets out the circumstances in which the 'M' number is recorded on the Supply Point Register

0410

Workgroup Report

20 December 2012

Version 2.3

Page 8 of 27

3 Solution

Modification 0410

This modification seeks to assign responsibility to the accountable party for gas consumed at a site following its connection to the network if it is not subsequently confirmed with a Shipper and all gas used by that site subsequently allocated. Where the Transporter creates the MPRN and issues it to any party other than a Shipper, then the Transporter shall be the responsible party. Where a Shipper requests an MPRN from a Transporter, then the Shipper shall become the responsible party. It is not intended that this proposal is retrospective in nature but should apply to connections to the Gas Transportation Network after the implementation date – it does not attempt to clear the backlog of Unregistered Sites that currently exist, which we believe should be resolved through a separate process.

There are currently provisions in the UNC which allow a site's consumption to be backdated to a Shipper if they provide the reading as at Meter Fix. We propose for this to continue and to apply to all cases where the Shipper has created the MPRN.

Changes to the AUGE process

This process will quantify the amount of Unidentified Gas being used by unregistered sites that connect to the network after the modification is implemented. It therefore will have an impact on the AUGE process.

Once this modification has been approved, we will be looking to modify the AUGE guideline document to specifically require the AUGE to take into account the information collated by Xoserve when dealing with Unregistered sites.

Business Rules

1. Scope of Process

- 1.1. The process described below will be initiated to determine whether a consumer premises that is assigned an MPRN is capable of offtaking gas (i.e. has a meter fitted), either without a Shipper being assigned to that site or off took prior to the Shipper confirmation. If found to have off-taken gas then the organisation that requested createdion of the MPRN will be charged for Unregistered Gas used, as estimated by Xoserve.
- 1.2. It does not apply when:
- 1.2.1. A premises has been connected to the network without being assigned an MPRN (this is covered by processes dealing with theft in conveyance).
- 1.2.2. A premises that has connected to the network and has been assigned an MPRN and gas been off-taken but has not had a meter fitted to an appropriate standard when investigated (this is covered by processes dealing with theft in conveyance).
- 1.2.3. A site has connected to the network and has been assigned an MPRN, but has not off-taken any gas as determined under section 3 of this document (site is currently adhering to the UNC provisions, specifically TPD G7.3.3).
- 1.2.4. A site has been connected to the network, assigned an MPRN, has initially off-taken gas without a Shipper registered, but all of the site's consumption is backdated in accordance with G7.3.7 or a registering Shipper has been allocated all of the unregistered consumption for that site.

0410

Workgroup Report

20 December 2012

Version 2.3

Page 9 of 27

1.3. This process will only apply to sites where an MPRN has been issued after the Modification has been implemented following an Authority decision.

2. Process Trigger

- 2.1. The process is triggered when a site that has been assigned an MPRN and:
- 2.1.1. Is registered to a Shipper from the Supply Point Confirmation date and Xoserve cannot allocate all of the energy consumed to a particular Shipper and/or-
- 2.1.2. Is visited in accordance with section 3.1 and, as a result of this visit, it is believed that the site falls under the classification detailed in section 1.1. The invoicing process as defined in section 6 will only be triggered once the criteria in 2.1.1 is met.
- 2.2 It is not expected that Xoserve should scrutinise each Shipper confirmation to ascertain that whether that site has flowed gas whilst Unregistered.

3. Site visits

- 3.1. The relevant Transporter will be required to visit every site in 12 months of the MPRN being created, where the site has not been registered with a Shipper or has not been disconnected had the service discontinuedfrom the system, unless informed by a Shipper of the status of the site prior to the visit. This will ensure that all Unregistered sites consuming gas are identified and safety and integrity of the network is maintained
- 3.2. As part of any site visit, the relevant Transporter will be expected to:
- 3.2.1. Determine whether the site falls under the scope of this process, as described in section 1.1 and so should be classified as an Unregistered Site.
- 3.2.2. Where it believes that the site has been offtaking gas, obtain all relevant information to enable it to estimate the consumption of the site.
- 3.3. The Transporter must provide the information referred in section 3.2 to Xoserve within 10 business days of the visit so that they may determine the amount of Unregistered Gas when the site is confirmed.
- 3.4. Where the organisation who created the MPRN is a Shipper, then the Transporter may seek to recover any reasonable costs incurred in visiting the site.
- 3.5. This process does not preclude the relevant Transporter from recovering its costs incurred under any part of this process from any third party.

4. Estimation of Gas Use

- 4.1. Xoserve will attempt to determine the gas used by the Unregistered Site ("Unregistered Gas") from the information available to it, as well through discussions with the Shipper or relevant Transporter (as applicable). In the absence of any supporting information, Xoserve may utilise recognised standards to determine gas consumption, such as the CSEP NEXA table for domestic properties, where possible. For the avoidance of doubt, Xoserve is expected to utilise its experience and judgement to make the best estimate of gas utilised it is not expected to be 100% accurate in all cases.
- 4.2. Once Xoserve has been made that a site may have flowed gas whilst

 Unregistered, If Xoserve believes it has insufficient information to adequately determine the level of Unidentified Gas, then it may request a site visit, which

0410

Workgroup Report

20 December 2012

Version 2.3

Page 10 of 27

- may be charged for under section 3 by the Transporters, which will be undertaken as soon as possible.
- 4.3 Xoserve will calculate the Unregistered Gas within [40 business days] where confirmation has occurred the process has been triggered. Where a site visit has been requested by Xoserve, the start point of the process will be taken from when the Transporter has provided the results of the site visit.
- 4.4. The Shipper or the Transporter may provide at any time an estimate of Unidentified Gas at the site, prior to the deadline for calculating the site's consumption. Xoserve will have sole discretion on whether to accept the estimate provided.
- 4.5. Unidentified Gas will be determined using the following mechanisms:
- 4.5.1. Where possible, from Meter Readings obtained through any site visit or from the customer (with appropriate CVs or other conversion measurements applied).
- 4.5.2. Where sufficient Meter Readings are not available the estimate will be determined from any information available through investigation all relevant industry parties, including meter asset manager. The investigation should also consider other relevant factors such as the size of the property, meter installation date, nature of gas use etc.
- 4.6. In all cases, the organisation providing the Unidentified Gas estimation will use all reasonable endeavours to estimate the total consumption at the site applicable to this process.
- 4.7. If it is determined that the site has not consumed any gas during the period it was an Unregistered Site, then Xoserve will not be expected to undertake any further activity with regard to that site.

5. Calculation of Gas Cost

- 5.1. The Gas Cost calculation process for the purposes of attributing the Unregistered Gas will only seek to determine the costs for Energy and will not be extended to Transportation charges.
- 5.2. The total cost of the Unregistered Gas ("Unregistered Gas Cost") will be determined by multiplying the Unregistered Gas <u>for that each day</u> for the site by the <u>average applicable daily SAP rate</u> <u>for the relevant period</u> as determined by the period of unallocated gas.

6. Unregistered Gas Charges

- 6.1. Xoserve will generate an adhoc invoice to recover the cost identified in section 5 at M+2 following calculation referenced in 4.3 above.
- 6.2. The Unregistered Gas Cost will be recovered from the organisation that created the MPRN (the Shipper or the relevant Transporter) at the next available opportunity by Xoserve, subject to section 6.1.
- 6.3 All payments will be into a neutrality pot ("The Unregistered Site neutrality pot"), which will be managed by National Grid Gas.

7. Process for when a Shipper has provided the meter fix date

7.1. G7.3.7 currently allows for a Shipper to be assigned a site's consumption back to the Meter Fix Date, where the same Shipper supplies the Meter Fix Date as well as the Supply Point Confirmation.

7.2. For LSP MP where:

0410

Workgroup Report

20 December 2012

Version 2.3

Page 11 of 27

- 7.2.1 The Shipper did not provide the Meter Fix Date, it may use the process detailed in G7.3.7 to have a site's consumption backdated to the Meter Fix Date, providing that suitable meter readings (which may be an estimate) are provided to reflect the site's consumption over that period.
- 7.2.2. The Shipper did not provide the Meter Fix Date, then the confirming Shipper may choose the day after the MPRN creation date to be a "virtual meter fix date" to which gas consumption will be backdated to, again providing suitable meter readings (which may be an estimate) to reflect the site's consumption over that period.
- 7.3 For SSP Meter Points where:
- 7.3.1 The Shipper may provide the Meter Fix Date in order to have a site's consumption allocated to the Meter Fix Date (i.e. use the process detailed in G7.3.7), using the MP AQ defined at MP Creation to allocate the site's consumption over that period.
- 7.3.2. Where the Shipper is not responsible at the Meter Fix Date, then the confirming Shipper may define the day after the MPRN creation date to be a "virtual meter fix date" to which gas consumption will be allocated to, using the MP AQ defined at MP Creation to allocate the site's consumption over that period.
- 7.4 A Shipper must use all reasonable endeavours to notify Xoserve of the Meter Fix Date along with the associated Meter Fix Reading if it is available to them.
- 7.5. Where the Shipper or Transporter has paid the Unregistered Gas invoice for a site and all or part of the Unregistered Gas has been subsequently registered to a Shipper at that site (such as through G7.3.7), then the Shipper or Transporter may claim back the invoiced amount pertaining to the relevant period.
- 7.6. An Unregistered Gas invoice may be asked to be withdrawn by a Shipper or Transporter if a site has been registered for part or all of the period in question, prior to the invoice due date. If only part of the Unregistered Gas has been accounted for, then Xoserve will raise a new invoice for the remaining Unidentified Gas in accordance with section 6.
- 7.7. No charges shall be redistributed payment will be made by Xoserve to the Shipper until sufficient Unregistered Gas charge payments have been received to cover the repayment, following existing UNC invoice timescales

8. Unregistered Gas Charges Redistribution

- 8.1. All monies contained within the Unregistered Site neutrality pot will be distributed on a monthly basis, at the same time as AUGE charges are levied on Shippers.
- 8.2. The Unregistered Gas Charges will be distributed amongst Shippers in accordance with their User SPC Aggregate AQ Proportion for the Smaller SPC class (as determined in accordance with TPD E10.5)

Modification 0410A

Modification of the UNC is required as follows:

1. Users will be obliged to ensure that Suppliers contracted to them do not commission or procure the installation of a Supply Meter at a New Supply Meter

0410

Workgroup Report

20 December 2012

Version 2.3

Page 12 of 27

Point in the absence of a supply contract (to be in force on and from the date of installation of the Supply Meter) with the relevant consumer.

- o The User will warrant such to the Transporter.
- The Transporter will take measures to identify New Supply Meter Points where a
 Meter Point Reference Number (MPRN) has been created (whether by the
 Transporter/UIP or a User) but which have been unregistered for a period of >12
 months after the date of implementation of this Modification Proposal.
 - For such New Supply Meter Points the Transporter will check industry data sources for evidence of activity which may indicate that gas is capable of flowing. These will include checking connections records, attempted confirmation/registration, RGMA data flows and Connection & Disconnection regulations notifications.
- 3. Where the Transporter identifies or becomes aware that a Supply Meter has been installed at a New Supply Meter Point at the request of a Supplier (this may be through site visits by emergency or maintenance engineers, attempted confirmations, RGMA data and Connection & Disconnection regulations notifications) and the corresponding Supply Point has not been registered by the relevant User within a period of 3 months;
 - The Transporter will undertake proactive measures which may include checking industry data sources or contact with the consumer to establish the source of the request to install the Supply Meter.
 - The Transporter will notify the relevant User of the absence of a Supply Point registration.
 - In the event the relevant User warrants that their Supplier did not request installation of the Supply Meter, the Transporter will proceed in accordance with (11)
 - o In the event that the relevant User cannot be identified, the Transporter will contact the Supplier to ascertain the identity of the preferred User.
 - Where it has been necessary to undertake a site visit for the purposes of validating the presence of a Supply Meter or for any reason which may be associated with the Supplier's request made under (3) any reasonable costs incurred may be levied to the relevant User.
- 4. The relevant User will be required within 1 calendar month to confirm or otherwise to the Transporter that a supply contract is in place between their Supplier and the relevant consumer.
- 5. Where the User confirms to the Transporter that a supply contract exists or a response is not received by the Transporters in accordance with (4) the relevant User will be required to register the relevant Supply Point within 1 calendar month of being notified by the Transporter that a Supply Meter has been installed at the request of the User's Supplier.
- 6. In the event that such registration does not occur in accordance with (5) the Transporter will within 1 calendar month register the relevant Supply Point on the Users' behalf.
- 7. Relevant Transportation and Energy charges will be retrospectively charged to the relevant User to the point of Supply Meter installation (the Meter Fix Date).
 - The Meter Fix Date may be identified by interrogating RGMA data and Connection & Disconnection regulations notifications.
 - For the avoidance of doubt, Transportation and Energy charges will only be retrospectively charged to the relevant User if their supplier instigated the Supply Meter installation (the Meter Fix Date).

0410

Workgroup Report

20 December 2012

Version 2.3

Page 13 of 27

- 8. In the event that a breach of the UNC has occurred contrary to (1) and the relevant User has notified the Transporter in accordance with (4) above that a supply contract does not exist between its Supplier and the consumer, the relevant User will either:
 - ensure that within 1 calendar month its Supplier procures a supply contract with the consumer and register the relevant Supply Meter Point. Note: the relevant User must advise the Transporter of this intended action as part of the above notification.
 - o take steps to seek removal of the Supply Meter within 1 calendar month.
- 9. In the event that a Supplier procures a supply contract, but registration in accordance with (8) does not occur, the Transporter will register the relevant New Supply Meter Point on the Users' behalf within 1 calendar month.
- 10. In the event the relevant User is unable to ensure its Supplier procures a supply contract or secure such Supply Meter removal the User will notify the Transporter providing a full explanation of the circumstances under which a Supply Meter was provided and installed in the absence of a supply contract.
 - The Transporter will record all relevant details and provide a report twice yearly to the Authority.
 - The Transporter will also provide a non-anonymised twice yearly report
 detailing breaches of the UNC contrary to (1) covering instances where a
 relevant User has not registered the Supply Meter Point in which a Supply
 Meter was fitted by its Supplier; the report will be issued to the Authority
 and all Users.
- 11. Where the Transporter identifies or becomes aware that a Supply Meter has been installed at a New Supply Meter Point but has no reasonable evidence that this was done at the request of a Supplier and the corresponding Supply Point has not been registered by a User within a period of 3 calendar months the Transporter will within 3 calendar months:
 - Investigate whether the consumer has sought or procured a supply contract.
 - Where such a contract does not exist, advise the consumer to obtain a supply contract as soon as possible.
 - Where a consumer fails to obtain a supply contract the Transporter will in normal circumstances seek to disconnect the supply of gas to the consumer. This will be subject to consideration being given to any applicable legislation, regulation or code of practice that requires the Transporter to do otherwise. Transporters will undertake actions pertaining to treatment of unregistered and shipperless sites in a manner consistent with the relevant prevailing Codes of Practice.
 - Where the consumer confirms they have obtained a supply contract, the Transporter will contact the relevant User for confirmation that a supply contract is in place.
 - If the User confirms a supply contract is in place they will be required to register the relevant New Supply Point within 1 calendar month of notification by the Transporter.
 - In the event that such registration does not occur, the Transporter will within 1 calendar month register the relevant New Supply Meter Point on the Users' behalf.

Workgroup Report

20 December 2012

Version 2.3

Page 14 of 27

- In the event that the relevant User warrants that a supply contract is not in place, the Transporter will advise the consumer, requesting they obtain a supply contract as soon as possible.
- In the event that the relevant User cannot be identified, the Transporter will contact the Supplier to ascertain the identity of the preferred User.
- 12. Where a consumer fails to obtain a supply contract the Transporter will in normal circumstances seek to disconnect the supply of gas to the consumer. This will be subject to consideration being given to any applicable legislation, regulation or code of practice that requires the Transporter to do otherwise. Transporters will undertake actions pertaining to treatment of unregistered and shipperless sites in a manner consistent with the relevant prevailing Codes of Practice.
- 13. Where the Transporter has received a notification in accordance with (10) it will perform the activities in (11 and 12) and will levy its reasonable costs incurred to the relevant User.
- 14. Where gas is found to be capable of flowing the Transporter will within 1 calendar month take steps (which may include contact with the relevant consumer) to identify whether the consumer has procured a supply contract with a Supplier.
- 15. Where the consumer confirms they have obtained a supply contract, the Transporter will contact the relevant User for confirmation that a supply contract is in place.
 - If the User confirms a supply contract is in place they will be required to register the relevant New Supply Point within 1 calendar month of notification by the Transporter.
- 16. In the event that such registration does not occur in accordance with (15) the Transporter will within 1 calendar month register the relevant New Supply Meter Point on the Users' behalf.
- 17. Relevant Transportation and Energy charges will be retrospectively charged to the relevant User to the point of Supply Meter installation (the Meter Fix Date).
- 18. Where the point of Supply Meter installation (the Meter Fix Date) is unknown, relevant Transportation and Energy charges will be retrospectively charged to the relevant User from the date the Transporter first became aware that a Supply Meter had been installed in accordance with (3)
- 19. In the event that the Transporter has made a site visit for the purposes of (14) and a Supplier is found to be present, any reasonable costs incurred may be levied to the relevant User.
- 20. Where the Transporter identifies that a service pipe has been or is planned to be installed but a Supply Meter is not present and capable of flowing gas the Transporter will continue to monitor the position.

Workgroup Report

20 December 2012

Version 2.3

Page 15 of 27

4 Relevant Objectives

Impact of the modification on the Relevant Objectives:		
Re	levant Objective	Identified impact
a)	Efficient and economic operation of the pipe-line system.	None
b)	Coordinated, efficient and economic operation of (i) the combined pipe-line system, and/ or (ii) the pipe-line system of one or more other relevant gas transporters.	None
c)	Efficient discharge of the licensee's obligations.	None
d)	Securing of effective competition: (i) between relevant shippers; (ii) between relevant suppliers; and/or (iii) between DN operators (who have entered into transportation arrangements with other relevant gas transporters) and relevant shippers.	Positive (0410 and 0410A)
e)	Provision of reasonable economic incentives for relevant suppliers to secure that the domestic customer supply security standards are satisfied as respects the availability of gas to their domestic customers.	None
f)	Promotion of efficiency in the implementation and administration of the Code	Positive (0410A)
g)	Compliance with the Regulation and any relevant legally binding decisions of the European Commission and/or the Agency for the Co-operation of Energy Regulators	None

Relevant Objective (d) Securing of effective competition: (i) between relevant shippers; (ii) between relevant suppliers; and/or (iii) between DN operators (who have entered into transportation arrangements with other relevant gas transporters) and relevant shippers.

This mModification 0410 identifies measures, which serve to mitigate the likelihood of Unregistered Sites. The impact of this is to promote cost targeting on those organisations that may resolve these issues and mitigate the risks of such costs being otherwise shared by the industry via the RbD and Unidentified Gas processes.

MThis modification 0410A identifies measures which serve to mitigate the likelihood of unregistered sites occurring and proposed remedies where such instances are identified. The impact of this is to promote cost targeting on individual Users and mitigate the risks of such costs being otherwise shared to the Users having Smaller Supply Points (and potentially Larger Supply Points via the AUGE mechanism). Such a mechanism must therefore be considered to facilitate competition in the gas market.

Other Workgroup participants were concerned that energy costs recovered by the Transporter would not be sufficient to fund the cost of the process and therefore they would need to recover the additional costs from Shippers and this would not further

0410 Workgroup Report

20 December 2012

Version 2.3

Page 16 of 27

this relevant objective.

Standard Special Condition A11.1 (f): so far as is consistent with subparagraphs (a) to (e), the promotion of efficiency in the implementation and administration of the network code and/or the uniform network code;

<u>Modification 0410A</u> The identifies measures identified within this Modification which are likely to bring about a reduction in the overall number of unregistered sites. User Registration of Supply Points capable of flowing gas is fundamental to the efficient operation of the UNC.

5 Impacts and Costs

Consideration of Wider Industry Impacts

No impacts on other industry developments are anticipated as a result of implementing these modifications.

Costs

Indicative industry costs – User Pays

Classification of the modification as User Pays or not and justification for classification

Modification 0410 is <code>[not]</code> proposed] to be User Pays. Any costs should be targeted on the responsible party. For example if the Transporter created the MPRN, then the costs associated with change should be borne by Transporters and the same for Shippers. Modification 0410A is not proposed to be User Pays.

Identification of Users, proposed split of the recovery between Gas Transporters and Users for User Pays costs and justification

Modification 0410 - Xoserve has previously indicated that <u>for the period October 2011 to September 2012</u>, 80% of new MPRNs were created by Transporters, with the remainder <u>by Shippers.approximately 8,000 MPRNs are created, 7,500 by the transporters, 500 by shippers. This gives a 93.75%: 6.25% transporter:shipper ratio.</u> Therefore costs should be split <u>890:210</u> transporter: shipper.

Proposed charge(s) for application of Users Pays charges to Shippers

Modification 0410 - The primary issue is creation of Unregistered sites on the system, so it is proposed that the shipper costs are recovered in proportion to market share, split by MPRN. The charging basis for Shippers will be an allocation of the development costs to each Shipper based upon each Shipper's number of supply points in proportion to the total number of all Shippers supply points as measured on the date of the implementation of the modification, excluding Unique Sites.

0410

Workgroup Report

20 December 2012

Version 2.3

Page 17 of 27

TBC

Impacts

Impact on Transporters' Systems and Process	
Transporters' System/Process	Potential impact
UK Link	Changes to Transporters systems will be required
Operational Processes	Changes will be required
User Pays implications	No implications have been identified

Impact on Users	
Area of Users' business	Potential impact
Administrative and operational	The industry will need to find a mechanism whereby the Shippers and Transporters are assigned costs associated with gas consumed at Unregistered Sites.
Development, capital and operating costs	Not considered significant
Contractual risks	Not considered significant
Legislative, regulatory and contractual obligations and relationships	Not considered significant

Impact on Transporters	
Area of Transporters' business	Potential impact
System operation	None
Development, capital and operating costs	0410 - It is expected that Transporters will undertake more site inspections to avoid incurrence of costs. 0410A - Medium level implementation costs would be incurred by Transporters as a consequence of implementing this modification
Recovery of costs	None
Price regulation	None



Where can I find details of the UNC Standards of Service?

In the Revised FMR for Transco's Network Code Modification

0565 Transco
Proposal for
Revision of
Network Code
Standards of
Service at the

following location: http://www.gasgovern ance.com/networkcod earchive/551-575/

0410

Workgroup Report

20 December 2012

Version 2.3

Page 18 of 27

Impact on Transporters	
Contractual risks	0410 - Transporters may need to adjust their siteworks contract to avoid incurring costs through this process.
Legislative, regulatory and contractual obligations and relationships	None
Standards of service	None

Impact on Code Administration	
Area of Code Administration	Potential impact
Modification Rules	None
UNC Committees	None
General administration	None

Impact on Code	pact on Code	
Code section	Potential impact	
Section G 3.8	0410 - Disablement of supply – can be expanded to cover the investigation and disconnection process	
Section G 7.2.2 and 7.3.3	0410 - Expand to give Transporters responsibility for gas off-taken following a siteworks new connection where no shipper is in place	

Impact on UNC Related Documents and Other Referenced Documents	
Related Document	Potential impact
	None
Network Exit Agreement (Including Connected System Exit Points) (TPD J1.5.4)	None
Storage Connection Agreement (TPD R1.3.1)	None
UK Link Manual (TPD U1.4)	None

Workgroup Report

20 December 2012

Version 2.3

Page 19 of 27

npact on UNC Related Documents and Other Referenced Documents	
Network Code Operations Reporting Manual (TPD V12)	None
Network Code Validation Rules (TPD V12)	None
ECQ Methodology (TPD V12)	None
Measurement Error Notification Guidelines (TPD V12)	None
Energy Balancing Credit Rules (TPD X2.1)	None
Uniform Network Code Standards of Service (Various)	None

Impact on Core Industry Documents and other documents	
Document	Potential impact
Safety Case or other document under Gas Safety (Management) Regulations	None
Gas Transporter Licence	None

Other Impacts	
Item impacted	Potential impact
Security of Supply	None
Operation of the Total System	None
Industry fragmentation	None
Terminal operators, consumers, connected system operators, suppliers, producers and other non code parties	None

Workgroup Report

20 December 2012

Version 2.3

Page 20 of 27

6 Implementation

Implementation for Modification 0410:

- 01 April 2013 if a decision is received prior to 01 December 2012
- 01 April 2014 if a decision is received after 01 December 2012 and prior to 01 December 2013
- If a decision is received after 01 October 2013 implementation should occur for the following 1 April that is at least 6 months after the decision date

Implementation for Modification 0410A:

Systems changes are likely to be necessary to facilitate implementation of this modification. As part of its development, consideration will need to be given to identifying an optimum timetable for implementation. Consequently an implementation date is not identified at this point.

The proposed changes would have a prospective effect only and would not apply to any 'backlog' of unregistered sites, which currently exists. For the avoidance of doubt no charges identified within this modification would be retrospectively applied to any User in respect of any period prior to the implementation date nor would any reregistration of the Relevant User in respect of a Supply Point be required in respect of any period prior to the implementation date.

0410

Workgroup Report

20 December 2012

Version 2.3

Page 21 of 27

7 The Case for Change

No further advantages or disadvantages identified to those set out above.

0410

Workgroup Report

20 December 2012

Version 2.3

Page 22 of 27

8 Legal Text

The Workgroup has not reviewed the Legal text for these modifications.

Text for Modification 0410

Text for Modification 0410A

TPD Section G Supply Points

Insert paragraph 2.12 as follows:

2.12 Unregistered New Supply Meter Points

- 2.12.1 Each User warrants to the Transporter that it will not (and where the User will not be the supplier) its supplier will not install or procure the installation of a Supply Meter at a New Supply Meter Point without first having a Supply Contract in place with the consumer. [BR1]
- 2.12.2 Each Transporter will from time to time identify any new Supply Meter Point Reference Numbers for which there has been no First Supply Point Registration Date in accordance with paragraph G7.3.4 for a period greater than 12 calendar months since the Supply Meter Point Reference Number was created and where the Transporter has evidence of a Supply Meter being in place which is capable of flowing gas the Transporter will take steps to establish who requested installation of the Supply Meter which may include making enquiries of the consumer. [BR2]
- 2.12.3 Pursuant to paragraph 2.12.2 where the Transporter obtains information that a supplier requested the installation of the Supply Meter and the User subsequently confirms this the Transporter will notify the relevant User that no Supply Point Registration is in place at the New Supply Meter Point and:
 - (a) where the User confirms that a Supply Contract is in place between the supplier and consumer or does not respond within 1 calendar month of being notified by the Transporter the relevant User will register such New Supply Meter Point in accordance with paragraph 2 or take steps to remove the Supply Meter within 1 calendar month, failing which the provisions of paragraph 2.12.4 shall apply; or
 - (b) where the User confirms within 1 calendar month that no Supply Contract exists between the supplier and consumer the User shall ensure the supplier procures a supply contract with the consumer and will register such New Supply Meter Point in accordance with paragraph 2 or procure removal of the Supply Meter within 1 calendar month. [BR3/4/5]
- 2.12.4 Where the User does not comply with the obligation to register such New Supply Meter Point in accordance with paragraph 2.12.3 (a) or (b) or 2.12.9 (a) the User shall be deemed to have granted the Transporter authority to register such New Supply Meter Point on its behalf and:

0410

Workgroup Report

20 December 2012

Version 2.3

Page 23 of 27

- (a) the First Supply Point Registration Date shall be deemed to be the Meter Fix Date or if this is not known the date the Transporter first became aware that a Supply Meter had been installed; and
- (b) for the purposes of calculating the Opening Meter Reading the

 Transporter shall use the Meter Reading taken at the time the

 Transporter identifies that the Supply Meter is physically connected to
 a System such that gas is capable of being offtaken (without further action being taken) from the Total System. [BR6/8/9/11]
- 2.12.5 The Registered User pursuant to 2.12.3, 2.12.4 or 2.12.9 (a) shall be liable for:
 - (a) all reasonable costs incurred by the relevant Transporter in accordance with the Siteworks Terms and Procedures (as defined in Section G7.2.2) where the relevant Transporter undertakes a visit for reasons including validating the presence of a Supply Meter or to carry out a disconnection in accordance with the Gas Safety (Installation and Use) Regulations 1998 and where the Supply Meter remains connected to a System such that gas is capable of being offtaken (without any further action being taken) from the Total System; and
 - (b) all reasonable costs incurred by the relevant Transporter in discharging its obligations under paragraph 2.12; and
 - (c) all charges (including without limitation Transportation Charges <u>and Energy Balancing Charges</u>) associated with such New Supply Meter Point from the Meter Fix Date or if this is not known the date the Transporter first became aware that the Supply Meter had been installed.
 - (d) Where the Registered User is liable for any charges in accordance with (c) above:
 - in respect of Energy Balancing Charges for Larger Supply Points, a reconciliation will be carried out in accordance with Section E6 and applied to the aggregate reconciliation process in accordance with Section E7.2; and
 - (ii) in respect of Energy Balancing Charges and any relevant Transportation Charges for Smaller Supply Points, the Aggregate LDZ AQ shall be adjusted in accordance with Section E7.7.

[BR7]

- 2.12.6 In the event that the User does not comply with the obligation to register such New Supply Meter Point in accordance with paragraph 2.12.3(b) because it is unable to ensure its supplier procures a Supply Contract or the removal of the Supply Meter, the User shall submit a report to the Transporter detailing the circumstances in which a Supply Meter was installed without a Supply Contract being in place and any subsequent action the User has taken to try to rectify this. [BR10/13]
- 2.12.7 Each Transporter will keep a record of any reports it receives under paragraph 2.12.6 and submit a report twice yearly:
 - (a) to the Authority giving details of the reports received from each User (on an attributable basis); and
 - (b) to the Authority and all Users of the number of incidences where a User has not complied with paragraph 2.12.1 (on an attributable basis). [BR10]

2.12.8 Further to paragraph 12.2.2, in the event that either:

(a) the User confirms that the supplier did not request installation of the Supply Meter and the relevant New Supply Meter Point has 0410

Workgroup Report

20 December 2012

Version 2.3

Page 24 of 27

- not been registered by a User within 3 calendar months of the Transporter becoming aware that a Supply Meter has been installed at a New Supply Meter Point; or
- (b) the User confirms that the supplier did request installation of the Supply Meter and the User has taken steps in accordance with paragraph 2.12.3 (b) to try and ensure the supplier procures a Supply Contract with the consumer but no Supply Contract is in place and the User has been unable to procure removal of the Supply Meter,

then the provisions of paragraph 2.12.9 shall apply.

- 2.12.9 The Transporter will within 3 calendar months advise the consumer to obtain a Supply Contract and:
 - (a) if the consumer confirms that a Supply Contract is already in place and the relevant User verifies this then the relevant User shall register such New Supply Meter Point in accordance with paragraph 2 within 1 calendar month of being notified to do so by the Transporter failing which the provisions of paragraph 2.12.4 shall apply; or
 - (b) if the consumer does not enter into a Supply Contract or the Transporter is unable to ascertain whether a Supply Contract is in place then the Transporter shall seek to disconnect the supply of gas to the consumer subject to any applicable legislation, regulation or Code of Practice.

0410

Workgroup Report

20 December 2012

Version 2.3

Page 25 of 27



9 Recommendation

The Workgroup invites the Panel to:

 AGREE that Modifications 0410 and 0410A should be returned to Workgroup so that the legal text and proposed amendments to the solutions can be assessed.issued to consultation.

0410


Workgroup Report

26 July 201207 December 2012

Version <u>2.2</u>0.4

Page 26 of 27





Workgroup Report

26 July 201207 December 2012

Version 2.20.4

Page 27 of 27